

**ESTIMATE FOR RENOVATION WITHIN SHIBPUR DINO BANDHU INSTITUTION (COLLEGE),
412/1, G. T. ROAD(S), HOWRAH - 711 102**

july, 2017

Sl. No.	Description of Items	Qty.	Unit	Rate	Amount (INR)
AUDITORIUM					
1	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC.				
a)	Two Coats				
i)	Solvent based interior grade Acrylic Primer	301.357	sq.m.		
2	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothening of surface.				
	Two Coats	301.357	sq.m.		
3	Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	53.301	sq.m.		
4	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary				
	On timber or plastered surface :				
	With super gloss (hi-gloss) -				
	Two coats (with any shade except white)	53.301	sq.m.		
5	Dressed wood work in post , plate , battens . etc. fitted & fixed complete (excluding the cost of bolts only, but including the cost of nails, screws etc.) (The quantum should be corrected upto three decimals)				
	Sal : siliguri	1.338	cu.m.		
6	Supplying, fitting and fixing 6 mm. thk. Tinted glass with necessary wooden beading (20 mm. x 20 mm.) above existing wooden door.	0.480	sq.m.		

7	Providing and fixing carpet flooring of imported loopile carpet of Divine/unitex/armstrong make of approved shade and colour in meeting room, cabins and open working area complete in all respect including fixing of 5 mm thick poly urethane foam rolls below the carpet. Rates quoted should include cost of adhesives, fixing , cutting welding of carpet etc complete in all respects.	18.109	sq.m.		
8	Providing and fixing 4 mm. thk. Veneer panelling over 19 mm. thk. BWR plywood surface at front part of the stage. The veneer is to be finished with natural melamine polish to match the décor	3.105	sq.m.		
9	Supplying and fixing of 3/4" dia 1 mm thick ,SS hollow tubes in 2 layers for the fixing of window curtains . The quoted rate shall inclusive of SS brackets on either side and one side with threaded clamp for the fixing and removal of rod to provide the curtain	10.000	R.mt.		
10	Supply and installation of cotton curtains lined 2 layers of fabric hemmed at the bottom and sides and top with eyelet ring stud.Samples shall be submitted for approval from Client/Architect.	24.384	sq.m.		
12	Providing & fixing of Podium as per design made of 19mm thick BWR plywood and 4mm thick veneer of approved shade. The veneer to be melamine polished, all complete as per design & direction of Architect / EIC.	1.000	each		
13	Renewing and repairing of existing wooden window at required position including supplying and fitting new teak wood members and finishing the same as directed.	0.150	cu.m.		
14	Supplying and laying true to line and level Double Charge Vitrified Tiles of approved brand conforming to IS 15622: 2006 (Group B I a) and tested as per IS 13630:2006 (relevant parts) [Non-modular sizes for tiles with Water absorption (av.) \leq 0.08 %] in floor, skirting etc. using polymerised adhesive of 6mm thick layer applied directly over finished artificial stone floor/Mosaic etc. without any backing course and joints grouted with admixture of white epoxy grout materials of approved brand including spacer - 2mm as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials,labour and all other incidental charges complete as per direction of Engineer-in-Charge.				
a	In Ground Floor:(size not less than 600 mm X 600 mm X 9.5 mm thick)	112.59	Sq. M.		
	TOTAL (The price quote should be excluding applicable GST. The contractor will be paid GST as applicable during final payment)				